

**Midland Project Management Pty Ltd
8500 12F George Scope and Budget**

**12F GEORGE STREET MIDLAND
SALE PROPERTY**

This schedule shall be read in conjunction with the Drawings, Specification and Addenda.
Not every item indicated on the drawings is listed on this schedule

SCHEDULE OF WORK

All trades shall ensure that all work complies with strata titling requirements.

EXTERNAL GENERAL

Refer to "12 George Street General External"

FRONT AND REAR YARDS

Garden Maintenance + Paver

Provide new fold down clothes hoist

Plasterer

Apply a sand render as per the drawings

Carport subcontractor

Provide new attached Ese Patio Design 2 (or equal) Colorbond carport as specified and per the site plan. Colour: TBA

HOUSE

Maintenance

Remove any street numbers and unused brackets/fixings off the building and make good.
Refix any loose mouldings and replace rotten barges and mouldings.
Provide roof framing for new gable as indicated

Electrician

Replace all existing external lights at front, rear and laundry doors with plastic bunker style fittings.
Provide a new bunker light fitting on carport wall with external 2 way switch

Plumber

Provide stormwater drains to all new downpipes and to existing downpipes where missing, all connected into the stormwater mains.

Roofer

Ensure that party wall extends to underside of roof cover and provide fire blanket along top of wall to close off between roof and wall.
Provide new gable tiling and roof plumbing
Ensure the roof is watertight and make good as specified
Pressure clean and paint the roof as specified- Colour TBA
Provide all new slotted gutters and downpipes all in Zinalume.
Make good all downpipe connections to stormwater drains

Brick Cleaner

Clean all external surfaces of the house. Note: facebrick will be painted

Glazier

Replace any broken/cracked/missing glass.
Replace all flywire.
Make good / provide new barrier doors and flyscreen doors as specified.
Re-putty timber windows where putty is missing or cracked and loose.

Painter

Midland Project Management Pty Ltd

8500 12F George Scope and Budget

Paint all paintable surfaces including facebrick and render as per Schedule of External Colours

INTERNAL GENERAL

Maintenance

Remove all rubbish, posters, etc and all curtains, blinds, other disused brackets/fixings
Remove all cabinets in kitchen, laundry and bathroom.
Strip off all wall tiles in kitchen, bathroom, and laundry and make good the walls ready for the tiler.
Leave all floor tiles.
Remove the fridge wall in the kitchen
Plaster the facebrick wall in the bedroom and bathroom (or line with 6mm Gyprock)
Make good damaged ceilings and wall linings
Make good wall and ceiling vents as specified
Provide white cushion buffers on the skirting behind all doors.
Refix loose mouldings and replace any badly damaged/missing mouldings
Ensure that all timber windows and doors operate correctly.
Replace all door hardware
Provide new door to bathroom on lift off hinges

Plumber

Have a licensed gas plumber test and check the existing gas plumbing work as specified and sign the attached statutory declaration
Have a licensed plumber test and check the existing plumbing work as specified and sign the attached statutory declaration

Electrician

Replace faulty, cracked, broken or missing light outlets and GPO's
Replace all switches and convert all single GPO into double outlets
Provide 200mm diameter glass sphere batten fix fittings with 60watt globes to all incandescent light outlets except bathroom and WC which shall be 100mm.
Provide new smoke alarm
Have a licensed electrician fit an RCD, check and test the existing electrical work as specified and sign the attached statutory declaration

Telecommunications

Ensure that there is at least one operational telephone outlet as specified

Flooring subcontractor

Remove loose floor coverings and prepare floors ready for carpet and sheet vinyl.
Provide glued down sheet vinyl to kitchen.
Provide carpet on underlay to lounge, passage and bedroom
Provide reducing strips at floor junctions where missing.

Tiler

Point up all benchtop/tile junctions and around edges of sinks/basins/troughs/baths with matching siliconised acrylic sealant.

Glazier

Ensure that all windows and doors operate correctly.
Replace missing or faulty door and window hardware

Painter

Remove all wallpaper, curtains, blinds, other disused brackets/fixings and make good.
Make good and paint the entire interior as per Schedule of Interior Colours

Window treatment

Midland Project Management Pty Ltd

8500 12F George Scope and Budget

Provide slim-line Venetian blinds to all windows except bathroom and WC

ENTRY AND LOUNGE

Maintenance

Provide new Project Hardware Ashley PH137RR leverset to the front door with matching separate double deadlock. Remove unused hardware including door seal and make good.

Plumber

Provide new gas bayonet.

Provide wall and ceiling vent to comply with Alinta gas regulations.

Electrician

Remove electric wall heater

KITCHEN

Plumber

Provide a new 1350mm bowl and a half inset sink and new single lever mixer sink mounted tap

Provide new gas stove connection

Electrician

Provide 1200mm long double 40 watt tube fluoro light with diffuser.

Provide a new 600mm rangehood flued through ceiling

Remove the existing ceiling fan

Provide new electrical outlets as per the sketch

Remove stove connection

Cabinetmaker

Replace the kitchen cupboards as per the attached drawing fitted with brushed aluminium/stainless steel C-pull-handles..

Tiler

Retile over benches and sink to underside cupboards

LAUNDRY

Maintenance

Provide new back door with separate deadlock and latchset, and Raven RP4 seal to back door

Remove unused hardware and make good.

Plumber

Provide new washing machine taps, 200mm swivel spout and taps to trough

Painter

Treat trough cabinet for rust and paint inside and out

Tiler

Retile over trough

Prepare floor, provide new grate to floor waste, and tile the entire floor including skirting

BATHROOM

Maintenance

Provide new 1200mm towel rail

Provide new white Caroma Bathmates paper holder

Plumber

Midland Project Management Pty Ltd
8500 12F George Scope and Budget

Provide new white close coupled dual flush toilet suite
Provide new taps, spout and white basin to the vanity
Provide new multi-directional shower rose and taps

Electrician

Provide an oyster style fluorescent fitting and a 250mm ceiling exhaust fan on same switch.
Provide a new GPO on wall next to the vanity

Cabinetmaker

Provide new 900mm long vanity unit to detail

Glazier

Replace the glass in the screen with clear glass
Provide a new 800 wide x 900mm high mirror on the wall adjacent to the vanity

Tiler

Waterproof walls and floor in the shower to comply with the BCA and retile over the full extent of the existing tiling including skirting. Provide soap dish
Tile 1c over vanity top
Retile floor and skirting all round

SCHEDULE OF INTERIOR COLOURS AND MATERIALS

Colour Scheme SAND – Refer attached schedule

NOTE Ensure schedules are titled specifically for this project