

<b>21 GARTRELL STREET MIDLAND</b>	
<b>SALE PROPERTY</b>	
This schedule shall be read in conjunction with the Drawings, Specification and Addenda.	
Not every item indicated on the drawings is listed on this schedule	
<b>SCHEDULE OF WORK</b>	
All trades shall ensure that all work complies with strata titling requirements.	
<b>EXTERNAL GENERAL</b>	
Refer to "21-23 Gartrell Street General External"	
<b>FRONT AND REAR YARDS</b>	
<b>Garden Maintenance + Paver</b>	
Provide new fold down clothes hoist	
<b>Plasterer</b>	
Apply a sand render as per the drawings. Provide protective tape as specified	
<b>HOUSE</b>	
<b>Maintenance</b>	
Remove any street numbers and unused brackets/fixings off the building and make good.	
Refix any loose mouldings and replace rotten barges and mouldings.	
Provide posts and roof framing etc for new gable as indicated	
<b>Electrician</b>	
Replace all existing external lights at front, rear and laundry doors with plastic bunker style fittings.	
Provide a new bunker light fitting on carport wall with external 2 way switch	
<b>Plumber</b>	
Provide stormwater drains to all new downpipes and to existing downpipes where missing, all connected into the stormwater mains.	
<b>Roofer</b>	
Provide new gable tiling and roof plumbing	
Ensure the roof is watertight and make good as specified	
Pressure clean and paint the roof as specified- Colour TBA	
Clean out all gutters and make good as specified.	
Remove and refix or renew downpipes after render is complete	
Make good all downpipe connections to stormwater drains	
<b>Brick Cleaner</b>	
Clean all external surfaces of the house. Note: facebrick will be rendered and painted	
<b>Glazier</b>	
Replace any broken/cracked/missing glass.	
Replace all flywire.	
Make good / provide new barrier doors and flyscreen doors as specified.	
Re-putty timber windows where putty is missing or cracked and loose.	
<b>Painter</b>	

Paint all paintable surfaces including facebrick and render as per Schedule of External Colours	
<b>INTERNAL GENERAL</b>	
<b>Maintenance</b>	
Remove all rubbish, posters, etc and all curtains, blinds, other disused brackets/fixings	
Remove all cabinets, sanitaryware and plumbing fixtures in kitchen, laundry, WC and bathroom including bath hob wall.	
Strip off all wall tiles in kitchen, bathroom, and laundry and make good the walls ready for the tiler. Leave all floor tiles.	
Remove wall between kitchen and dining as per the sketch	
Make good damaged ceilings and wall linings	
Make good wall and ceiling vents as specified	
Provide white cushion buffers on the skirting behind all doors.	
Refix loose mouldings and replace any badly damaged/missing mouldings	
Ensure that all timber windows and doors operate correctly.	
Replace all door hardware	
<b>Plumber</b>	
Have a licensed gas plumber test and check the existing gas plumbing work as specified and sign the attached statutory declaration	
Have a licensed plumber test and check the existing plumbing work as specified and sign the attached statutory declaration	
<b>Electrician</b>	
Replace faulty, cracked, broken or missing light outlets and GPO's	
Replace all switches and convert all single GPO into double outlets	
Provide 200mm diameter glass sphere batten fix fittings with 60watt globes to all incandescent light outlets except bathroom and WC which shall be 100mm.	
Check the existing smoke alarm	
Have a licensed electrician fit an RCD, check and test the existing electrical work as specified and sign the attached statutory declaration	
<b>Telecommunications</b>	
Ensure that there is at least one operational telephone outlet as specified	
<b>Flooring subcontractor</b>	
Remove loose floor coverings and prepare floors ready for carpet and sheet vinyl.	
Provide glued down sheet vinyl to kitchen and dining/family room.	
Provide carpet on underlay to lounge, passage and all bedrooms	
Provide reducing strips at floor junctions where missing.	
<b>Tiler</b>	
Point up all benchtop/tile junctions and around edges of sinks/basins/troughs/baths with matching siliconised acrylic sealant.	
<b>Glazier</b>	
Ensure that all windows and doors operate correctly.	
Replace missing or faulty door and window hardware	
Provide keys for existing window locks	
<b>Painter</b>	
Remove all wallpaper, curtains, blinds, other disused brackets/fixings and make good.	
Make good and paint the entire interior as per Schedule of Interior Colours	

<b>Window treatment</b>	
Provide slim-line Venetian blinds to all windows except bathroom and WC	
<b>ENTRY AND LOUNGE</b>	
<b>Maintenance</b>	
Provide new Project Hardware Ashley PH137RR leverset to the front door with matching separate double deadlock. Remove unused hardware including door seal and make good.	
<b>Plumber</b>	
Provide new gas bayonet. Remove old floor brackets	
Provide wall vent to comply with Alinta gas regulations.	
<b>KITCHEN</b>	
<b>Plumber</b>	
Provide a new 1350mm bowl and a half inset sink and new single lever mixer sink mounted tap	
<b>Electrician</b>	
Provide 1200mm long double 40 watt tube fluoro light with diffuser.	
Provide a new 600mm rangehood flued through ceiling	
Remove the existing ceiling fan	
Provide new electrical outlets as per the sketch	
<b>Cabinetmaker</b>	
Replace the kitchen cupboards as per the attached drawing fitted with brushed aluminium/stainless steel C-pull-handles..	
<b>Tiler</b>	
Retile over benches and sink to underside cupboards	
<b>LAUNDRY</b>	
<b>Maintenance</b>	
Provide new separate deadlock and latchset, and Raven RP4 seal to back door	
Remove unused hardware and make good.	
Remove overhead cabinet	
<b>Plumber</b>	
Provide new washing machine taps and taps and swivel spout to trough	
Provide a new 45l steel cabinet trough	
<b>Tiler</b>	
Retile over trough and bench to 600mm	
Prepare floor, provide new grate to floor waste, and tile the entire floor including skirting	
<b>WC</b>	
<b>Maintenance</b>	
Provide new white Caroma Bathmates paper holder	
Remove the grip rail	
<b>Plumber</b>	
Provide new white close coupled dual flush toilet suite	
<b>Tiler</b>	

Prepare floor, provide new grate to floor waste, and tile the entire floor including skirting	
<b>BATHROOM</b>	
<b>Maintenance</b>	
Provide new 1200mm towel rail	
Remove the grip rail and shaving cabinet	
<b>Plumber</b>	
Provide new taps, spout and white basin to the vanity	
Provide new multi-directional shower rose and taps, bath taps and spout	
Provide a new white shower bath	
<b>Electrician</b>	
Provide an oyster style fluorescent fitting and a 250mm ceiling exhaust fan on separate switch.	
Provide a new GPO on wall next to the vanity	
<b>Cabinetmaker</b>	
Provide new 850mm long vanity unit to detail	
<b>Glazier</b>	
Provide new 450mm wide shower screen with curtain rod on the edge of the bath at the tap end. Return rod into side wall 300mm short of the vanity and provide dropper support off the ceiling	
Provide a new nominally 490 wide x 900mm high mirror on the wall over the vanity	
<b>Tiler</b>	
Seal between bath and walls, waterproof walls to comply with the BCA and retile over the full extent of the bath to 1950mm including bath upstand end shelf and skirting all round. Provide soap dish	
Tile 1c over vanity top	
Retile floor and skirting all round	
<b>SCHEDULE OF INTERIOR COLOURS AND MATERIALS</b>	
Colour Scheme – Refer attached schedule	